R 805

Technical Report

R 805

Sponsored by

NAVAL FACILITIES ENGINEERING COMMAND

March 1974

CIVIL ENGINEERING LABORATORY
NAVAL CONSTRUCTION BATTALION CENTER
Port Hueneme, California 93043

Navy submersible TURTLE
performing inspection of
concrete spheres.

LONG-TERM DEEP-OCEAN TEST OF CONCRETE SPHERICAL STRUCTURES—

Part I: Fabrication, Emplacement, and Initial Inspections

by Harvey H. Haynes

Approved for public release; distribution unlimited.

74
417
N3
no. R 805

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER TR-805	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) LONG-TERM DEEP-OCEAN TEST OF CONCRETE SPHERICAL STRUCTURES—Part I: Fabrication, Emplacement, and Initial Inspections		5. TYPE OF REPORT & PERIOD COVERED Not final; July 1971—June 1973
7. AUTHOR(s) Harvey H. Haynes		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS CIVIL ENGINEERING LABORATORY Naval Construction Battalion Center Port Hueneme, California 93043		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS Naval Facilities Engineering Command Alexandria, VA 22332		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 3.1610
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE March 1974
		13. NUMBER OF PAGES 43
		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Concrete structures, pressure-resistant structures, concrete spheres; permeability, implosion, submerged concrete structures, seawater permeability of concrete, long-term loading, unreinforced concrete.		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report summarizes the fabrication, emplacement and inspections during the first 1.2 years of submergence of eighteen 66-inch-OD concrete spheres. The spheres are located 4 miles south of Santa Cruz Island, California, in depths of water from 1,840 to 5,075 feet. The purpose of the test is to collect data on time-dependent failure, permeability and durability of concrete pressure-resistant structures. Findings from the inspections showed that two spheres located at the depths of 3,725 and 4,330 feet had imploded and that the		

DD FORM 1 JAN 73 1473 EDITION OF 1 NOV 65 IS OBSOLETE

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

MBL/WHOI

0 0301 0040410 9

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

20. Continued

quantity of seawater which permeated through the concrete for phenolic-coated spheres was about 0.8 cu ft and for uncoated spheres it was about 1.6 cu ft. This test program is planned to continue through 1981 (total of 10 years).

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

CONTENTS

	page
INTRODUCTION	1
TEST DESCRIPTION	1
FABRICATION	2
EMPLACEMENT	5
INSPECTIONS	10
RESULTS	10
Implosion	10
Permeability	13
SUMMARY	16
ACKNOWLEDGMENTS	17
REFERENCES	18
APPENDIXES	
A — Concrete Materials	19
B — Soil Properties	27
C — Compressive Strength of Concrete for Sphere 3	28
D — Calculation of Seawater Intake	31
LIST OF SYMBOLS	35

INTRODUCTION

Numerous experimental studies have been performed at the Civil Engineering Laboratory (CEL)^a on the behavior of concrete structures under hydrostatic loading [1-11].^b These studies have shown that concrete is well suited as a construction material for pressure-resistant structures to depths of 3,000 feet. The empirical data were obtained from test specimens subjected to relatively short-term loading conditions where the longest loading-period for any specimen was 42 days. This series of ocean tests was conducted to supplement the earlier research by providing data on concrete structures subjected to in-situ deep-ocean conditions for periods of up to 10 years.

The objectives of the test program were to obtain design information on time-dependent failure, permeability, and durability of the concrete spheres. Data on time-dependent failure will permit a rational factor of safety to be applied to pressure-resistant structures; data on seawater permeability of concrete will allow predictions of the quantity of water to be expected to penetrate to the structure's interior; and data on the durability of plain and steel reinforced concrete will determine such factors as strength changes with time, chemical composition changes of the concrete, and steel corrosion problems.

TEST DESCRIPTION

Eighteen, 66-inch-OD concrete spheres were placed in the ocean at depths ranging from 1,840 to 5,075 feet (Table 1). This depth range corresponds to a sustained pressure-to-short-term implosion pressure

ratio, P_s/P_{im}^c of 0.36 to 0.83. It was anticipated that the spheres subjected to a P_s/P_{im} ratio of 0.70 or greater would implode with time [8]; therefore, the six spheres at greatest depths were equipped with clocks that would count days in periods up to three years. If a sphere imploded, the clock would record the day of failure.

Permeability data will be gathered using the following method: the spheres are buoyant by approximately 1,000 pounds and are tethered 32 feet off the seafloor by a 2-1/4-inch-diameter chain. As seawater permeates the concrete, the weight of the sphere will increase. The reduced buoyancy of the sphere means less chain can be suspended off the seafloor, so the sphere moves closer to the seafloor. A change in height of one chain link (2-1/4-inch chain) corresponds to 0.5 cu ft of seawater which has permeated to the hull interior.

The permeability rate of seawater through waterproofed and nonwaterproofed concrete will be determined. Eight spheres were coated on the exterior with a two-part phenolic coating; another eight spheres remained uncoated. All sixteen of these permeability specimens were of unreinforced concrete. The remaining two spheres were reinforced with conventional steel bars of 0.5-inch diameter. The reinforcement was covered with 1 or 2.5 inches of concrete. Also, one-half of the exterior of each sphere was coated with the phenolic compound while the other half remained uncoated.

The durability of the concrete will be studied by determining the changes in strength and chemical composition with time. The concrete compressive strengths will be obtained from core specimens drilled from 14 x 18 x 18-inch blocks. Blocks are located with the spheres in the deep ocean and on land,

^a Formerly the Naval Civil Engineering Laboratory; now a detachment of the Naval Construction Battalion Center, Port Hueneme, California.

^b Numbers in brackets indicate references.

^c The short-term implosion pressure, P_{im} , is calculated by the following empirical equation [8]:

$$P_{im} = [5.02(t/D_o) - 0.038] f'_c$$

Table 1. Test Description

Sphere No.	Depth (ft)	P_s/P_{im}^a	Concrete Water-proofed	Comments
1	5,075	0.83	Yes	clock inside sphere
2	4,875	0.80	Yes	clock inside sphere
3	4,330	0.72	Yes	clock inside sphere
4	4,185	0.81	No	clock inside sphere
5	4,100	0.78	No	clock inside sphere
6	3,875	0.70	No	clock inside sphere
7	3,725	0.58	Yes	
8	3,665	0.60	Yes	
9	3,295	0.62	No	
10	3,190	0.56	No	
11	3,140	0.50	Yes	
12	2,790	0.55	No	
13	2,635	0.41	Yes	
14	2,440	0.44	Yes	
15	2,300	0.43	No	
16	2,120	0.40	No	
17	1,980	0.38	<i>b</i>	steel reinforcement in walls
18	1,840	0.36	<i>b</i>	steel reinforcement in walls

^a Sustained pressure-to-short-term implosion pressure ratio.

^b One hemisphere is waterproofed while the other hemisphere is not waterproofed.

exposed to ambient conditions. Chemical composition changes of the concrete will be determined by comparing x-ray diffraction patterns with those of the concrete at age 20 months.

FABRICATION

Concrete hemisphere sections were cast in a steel mold and the following day were removed from the mold. Twelve 6 x 12-inch-long control cylinders and one 14 x 18 x 18-inch control block of concrete were also cast with each hemisphere.

Moist-curing of the hemisphere, six control cylinders, and the control block was accomplished by wrapping the specimens in wet burlap and then in polyethylene film: the remaining six control cylinders were placed in the fog room. Moist-curing continued for 28 days at ambient temperature inside an open building followed by 28 days of room-curing conditions, and then on-land field-curing conditions.

After several weeks of field curing, the hemispheres were prepared for assembly into spheres. The equatorial edges were ground flat by using a large steel plate, and silica carbide grit and water as the cutting agent. A titanium hull penetration at the apex

Figure 1. Fabrication of spheres.

of each hemisphere was epoxy-bonded into place. The exterior surfaces of the hemispheres were lightly sand blasted and a two-part phenolic compound (Phenoline No. 300) was applied.^d Finally, to fabricate a sphere two hemispheres were bonded together with an epoxy adhesive (Furane Epocast 8288). Figure 1 shows several of these operations.

All of the spheres had the same dimensions and variations in out-of-roundness. Extensive measurements [8] were taken on one hemisphere, and Table 2 summarizes the dimensions. In summary, the mean outside diameter was 65.886 inches and the mean wall thickness was 4.124 inches.

Conventional 1/2-inch-diameter steel reinforcing bars were embedded in the concrete of two spheres. Arrangement of the steel bars is shown in Figure 2. Alternate longitudinal bars had a nominal concrete cover of 1 or 2.5 inches; however, in certain locations near the apex the minimum cover was as low as 0.5 inch.

Clocks were placed in Spheres 1 through 6 to record the day of implosion, if the sphere should fail. The clock records days on a counter and has a projected life of 3 years.^e Figure 3 shows the clock and its pressure housing which was a 4-inch-OD pipe section. The pipe was attached to the top penetrator of the sphere.^f

^d Pinholes existed in the final waterproof coating at a rate of approximately 1 per 2 sq in.

^e For zero time in the ocean, the clocks read 41 days for Spheres 1-3, and 38 days for Spheres 4-6.

^f Upon retrieval, safety precautions should be followed in handling the pressure housing because water at high pressure could be inside. Prior to opening, drill a 1/8-inch-diameter hole through the steel wall to relieve any internal pressure.

Figure 2. Arrangement of steel bar reinforcement for Spheres 17 and 18.

Figure 3. Clock mechanism and its 4-in.-OD pressure housing.

Table 2. Hemisphere Dimensions and Out-of-Roundness Variations

Item	Mean Dimension (in.)	Standard Deviation		Maximum Local Variation	
		Measured (in.)	Percent of Wall Thickness	Measured (in.)	Percent of Wall Thickness
Interior radius	28.820	± 0.093	± 2.26	+0.145 -0.213	+3.51 -5.16
Exterior radius	32.943	± 0.083	± 2.01	+0.150 -0.247	+3.64 -5.94
Wall thickness	4.124	± 0.060	± 1.45	+0.181 -0.165	+4.26 -3.90

Power was supplied to the clock from dry-cell batteries placed in a watertight, but not pressure-resistant container located at the bottom of the sphere. When implosion occurs, the batteries are destroyed or shorted, and the lead wires running to the clock are broken.

Final assembly of the spheres is shown in Figures 4 and 5. The descriptive information on Figure 5 gives important details on the assembly.

Documentation of the concrete material is given in Appendix A. The mix proportions, compressive strengths, cement compositions, and x-ray diffraction

patterns of the concrete are presented. In general, the concrete was made from a high-quality mix design where the cement factor was 7.8 sacks per cu yd and water-cement ratio was 0.40; the compressive strength at 28 days was an average 7,660 psi.

Disposition of the control cylinders and blocks is as follows: of the six control cylinders placed in the fog room, three were tested at 28 days; their compressive strengths are given in Appendix A, Table A-2. The remaining three control cylinders will stay in the fog room and will be tested when the spheres are retrieved from the ocean. Three of the six control cylinders cured with the hemisphere were tested at age 28 days and the remaining three were tested approximately one month prior to emplacing the spheres in the ocean (Table A-2); these later tests gave the compressive strength used in calculating the short-term implosion pressure, P_{im} . There were two control blocks per sphere; one block went with the sphere into the ocean and the other block stayed on land, located within 50 yards of the ocean. Both blocks will be cored and tested when the sphere is retrieved.

EMPLACEMENT

The spheres were emplaced in the ocean 4 miles south of Santa Cruz Island, California (Figure 6), on 23 September 1971. The method of emplacing the spheres was as follows: a barge loaded with the spheres (Figure 7) was towed by a surface vessel (USNS *Gear*) which maintained a constant course over a location where the seafloor increased in depth at a fairly uniform rate. At predetermined depths, the appropriate sphere was pushed overboard to free-fall to the seafloor. The method worked well with most of the spheres landing within a few hundred yards of the target location. Final location of the spheres is given in Table 3. Figure 8 shows a plan view and Figure 9 a profile view of the sphere locations.

Water samples were obtained from the depth of 2,530 feet and gave the following data: temperature of 5.33°C, salinity of 34.41 ppt, pH of 7.2, oxygen content of 0.06 ml/l, and velocity of sound of 1,483.9 m/sec. A water sample from 4,740 feet gave a temperature of 5.16°C and a pH of 7.0.

Figure 4. Final assembly of sphere.

* Note: Items b, c, d, e, f, and g were used with only Spheres 1-6.

Figure 5. Details of sphere assembly.

Table 3. Location of Spheres

Sphere No.	Surface Location at Launch				Seafloor Location Found by <i>Turtle</i>				Depth (ft)	Sphere No.				
	Lorac Coordinates		Distance Between Spheres (yd)	Azimuth Between Spheres (°T)	Lorac Coordinates		Distance Between Spheres (yd)	Azimuth Between Spheres (°T)						
					G	R								
1	479.6 ^a	324.4	680	346	490.0	302.0	400	349	5,075	1				
2	481.5	320.0							4,875	2				
3	489.9	305.2	2,400	340					4,330	3				
4	491.4	302.6	600	341					4,185	4				
5	492.6	300.8	200	340					4,100	5				
6	501.9	284.3	2,650	344	500.0	280.9	800	326	3,875	6				
7	503.2	282.2	400	344					3,725	7				
8	506.6	277.1	900	343					504.7	277.2	3,665	8		
9	511.2	268.0	1,580	350					509.0	265.5	1,920	352	3,295	9
10	511.7	266.6	280	350					511.7	264.4	380	309	3,190	10
11	516.0	259.3	1,250	345	523.5	249.5	970	280	3,140	11				
12	524.4	250.8	1,720	337					1,650	339	2,790	12		
13	527.0	248.0	540	337					532.5 ^b	249.7	332	2,635	13	
14	528.8	244.4	650	347					536.1 ^b	246.8	630	332	2,440	14
15	530.2	242.4	400	355					534.6	242.6	700	23	2,300	15
16	531.7	240.8	300	345	535.0	239.5	550	5	2,120	16				
17	533.0	239.4	300	324					200	10	1,980	17		
18	534.0 ^c	238.3	200	352					200	347	1,840	18		

^a Geographic coordinates 33 $^{\circ}$ 49'15"N by 119 $^{\circ}$ 33'30"W.^b These locations may be in error.^c Geographic coordinates 33 $^{\circ}$ 56'15"N by 119 $^{\circ}$ 36'15"W.

Figure 6. Location of spheres off California coast.

Figure 7. Spheres rigged on barge in preparation for free-fall launch.

Figure 8. Plan view of sphere location.

Figure 9. Bottom profile at sphere location directly below surface launch.

A soil sample was obtained at the depth of 4,100 feet near Sphere 5. Data from the core are presented in Appendix B, Table B-1.

INSPECTIONS

Three inspection visits have been made to view as many spheres as possible. Of the 18 spheres, 15 have been viewed once, and of those 15, five have been viewed twice.

The first and third inspections were made by the Naval Submarine Development Group One using the submersible *Turtle*. The second inspection was made by Scripps Institution of Oceanography using the Remote Underwater Manipulator (RUM).

Turtle is a manned submersible capable of operating to depths of 6,500 feet. During the inspections with the submersible, however, those spheres at depths greater than 3,800 feet were not inspected because of the possibility of implosion of a test sphere. Investigators with the *Turtle* were

successful in inspecting Spheres 7-18. The spheres at greater depths (1-6) were to be inspected with the unmanned RUM vehicle. Within the time available for the inspection cruise with RUM, Spheres 3-5 were inspected successfully; the remaining spheres (1, 2, and 6) have not been inspected.

Data collected during the inspections are given in Table 4. The chain link count is the number of links of chain suspended off the seafloor by the buoyant spheres. If a sphere was found imploded or if anything unusual was observed, this information was recorded. Figures 10 and 11 show an uncoated sphere and a coated sphere tethered off the seafloor.

RESULTS

Implosion

Two spheres, 3 and 7, have imploded. Fragments of Sphere 3 were observed during the RUM inspection to be scattered over an area of what appeared to

Figure 10. View of uncoated sphere (No. 12) at a depth of 2,790 feet after 431 days.

Figure 11. View of coated sphere (No. 13) at a depth of 2,635 feet after 431 days. Material on top of sphere is sediment. Nylon rope on left side of sphere was used to secure 5/8-in. chain around sphere (see Figure 4).

be a 25-yard radius. To retrieve the clock, the manipulator on RUM picked up the 5/8-inch chain to which the clock was attached. Once on the surface, it was learned that the clock was not retrieved. Implosion forces must have "blown" the clock off the chain. Hence, the time to implosion for Sphere 3 was not obtained; however, from information obtained during the third inspection it has been deduced that the sphere imploded during descent. The *Turtle* operators thoroughly searched the Sphere 3 site for the clock, which was not located, but observations showed that fragments of concrete were spread over a radius of 50 yards. Also, the anchor chain was not at the center of debris or at the location of highest fragment density. This information

meant that the sphere probably imploded during descent which allowed the fragments to disperse.

In the case of Sphere 7, the fragments were all located within a 10-yard radius. Sphere 7 did not contain a clock, so the time to implosion is between 1 and 431 days.

For Spheres 3 and 7, the P_s/P_{im} ratio was 0.72 and 0.58, respectively. This level of long-term loading was considered relatively low for implosion to occur. However, seven other spheres are subjected to P_s/P_{im} ratios greater than 0.58, four of which have been inspected and are performing well.

The concrete control block for Sphere 3 was retrieved. The compressive strengths of this block and other control specimens stored at on-land field

Table 4. Inspection Data

Sphere No.	Chain Link Count ^a at--				Time to Implosion (days)	Comments
	Emplacement (By: CEL Date: 23 Sep 71 Time: 0 days)	Inspection No. 1 (By: <i>Turtle</i> Date: 4 Mar 72 Time: 163 days)	Inspection No. 2 (By: RUM Date: 26 Aug 72 Time: 340 days)	Inspection No. 3 (By: <i>Turtle</i> Date: 1 Dec 72 Time: 431 days)		
1	29.7 ^b	—	—	—	—	Insp. No. 3, observed sphere intact and floating high.
2	29.7	—	—	—	—	
3	29.4	—	imploded	—	0	
4	29.4	—	23	—	—	
5	29.6	—	21	—	—	
6	29.6	—	—	—	—	
7	31.5	—	—	imploded	1-431	
8	31.5	—	—	0	—	
9	31.6	—	—	—	—	
10	31.6	—	—	24	—	
11	38.0	—	—	31	—	Insp. No. 3, sphere intact but on seafloor. Insp. No. 3, chain tangled on block.
12	32.1	—	—	24	—	
13	32.1	28	—	28	—	
14	48.4	39	—	39	—	
15	32.2	26	—	25	—	
16	31.8	26	—	25	—	
17	32.6	29	—	28	—	
18	32.6	—	—	25	—	

^a Number of links suspended off seafloor by buoyant sphere.

^b Calculated number of links suspended off seafloor by sphere with concrete at room dry condition.

conditions and fog-room conditions are given in Appendix C. The control block from Sphere 7 was not retrieved as the *Turtle* was not rigged for a retrieval operation.

Permeability

The method used to determine the permeability of seawater through the concrete walls produced a fairly accurate indication of in-situ permeability behavior of the spheres. This method used the change in number (reduced number) of chain links to calculate the gain in weight of the sphere due to seawater intake. The accuracy of the quantitative results depend on several approximations; these are discussed in Appendix D. The accumulative effect of these approximations is estimated to be a maximum of ± 0.8 cu ft of seawater. This error can be reduced to ± 0.3 cu ft by comparing the change in link counts from actual inspections instead of using the calculated link count from zero days.

Table 5 gives the total quantity of seawater intake, Q , for the different time intervals between emplacement and inspections. Seawater intake includes the seawater absorbed by the concrete and the seawater that permeated through the concrete. Figure 12 shows the Q versus time behavior. Three items of interest are observed. One item is that the uncoated concrete spheres have a greater Q than the coated spheres; after 431 days, the coated spheres showed an average Q of about 2.6 cu ft and the uncoated spheres about 3.6 cu ft. Another item is that the spheres which have been inspected twice showed a considerable decrease in the rate of seawater intake. The last item is that Q increased for specimens at greater depth, but the increase was not pronounced.

The actual quantity of seawater permeating the wall, Q_p , was estimated by subtracting the quantity of absorbed seawater from the total seawater intake. Earlier work on 66-inch-OD spheres [8] showed that the concrete (same concrete as used in this study) absorbed approximately 3 percent by weight (or 7 percent by volume) of seawater. This corresponds to 2.0 cu ft of seawater absorbed by the concrete. Table 5 shows the Q_p values for the different time intervals. At 431 days, the average Q_p for the coated spheres was 0.8 cu ft and for the uncoated spheres was 1.6 cu ft.

Reference 8 reports permeability results from two 66-inch-OD concrete spheres subjected to seawater hydrostatic pressure tests. The permeability data are shown in Table 6. D'Arcy's permeability coefficient, K_c , was determined from the data as an average of 0.13×10^{-12} ft/sec. D'Arcy's permeability coefficient can be expressed as follows for the spheres:

$$K_c = \frac{Q_p t}{T A h} \quad (1)$$

where K_c = permeability coefficient, ft/sec

Q_p = quantity of permeability
seawater, cu ft

T = time, sec

t = wall thickness, ft

A = exterior surface area, cu ft

h = depth (or pressure head), ft

Using the K_c value of 0.13×10^{-12} ft/sec as a baseline, the data from the spheres in the ocean can be compared to that from the pressure vessel tests. Table 5 lists the K_c values for the ocean spheres. In all cases, the permeability coefficient was lower for the spheres in the ocean than for the spheres in the pressure vessels. The average K_c values for the coated spheres were 0.06×10^{-12} ft/sec at 163 days and 0.02×10^{-12} ft/sec at 431 days, and for the uncoated spheres were 0.11×10^{-12} ft/sec at 163 days and 0.06×10^{-12} ft/sec at 431 days. Other K_c values were those attained between the time interval of 163 to 431 days; for the coated spheres, no increase in Q_p was observed, so K_c was zero, and for the uncoated spheres the average K_c was 0.04×10^{-12} ft/sec.

The permeability data from the pressure vessel tests showed that a straight line curve of Q_p versus $\log T$ fit the data with fair accuracy. The empirical semi-log relations⁸ for one sphere (specimen CWL-9A) at a simulated depth of 2,520 ft was:

$$Q_p = 0.34 \log_{10} T - 0.11 \quad (2)$$

⁸ Equations 2 and 3 are presented in this report with time, T , in days. These equations are different from those in Reference 8 which give time, T , in hours.

Table 5. Permeability Data

Sphere No.	Concrete Water-proofed	Depth (ft)	Change in Link Count, ΔL , and Total Seawater Intake, Q , for—						Seawater Permeating Interior, Q_p , ^a and D'Arcy's Permeability Coefficient, K_c , for—					
			0-163 Days		0-340 Days		0-431 Days		163-431 Days		0-163 Days		0-340 Days	
			ΔL (links)	Q (cu ft)	ΔL (links)	Q (cu ft)	ΔL (links)	Q (cu ft)	ΔL (links)	Q (cu ft)	Q_p (cu ft)	K_c ft/sec $\times 10^{-12}$	Q_p (cu ft)	K_c ft/sec $\times 10^{-12}$
4	no	4,185	—	—	—	3.1	—	—	—	—	1.1	0.03	—	—
5	no	4,100	—	—	—	4.2	—	—	—	—	2.2	0.07	—	—
10	no	3,190	—	—	7.6	3.7	—	—	—	—	—	—	1.7	0.05
11	yes	3,140	—	—	7.0	2.8	—	—	—	—	—	—	0.8	0.02
12	no	2,790	—	—	8.1	3.9	—	—	—	—	—	—	1.9	0.07
13	yes	2,635	4.1	2.0	4.1	2.0	0	0	0	0	—	—	0	0
14	yes	2,440	9.4	3.1	9.4	3.1	0	0	1.1	0.12	—	—	1.1	0.04
15	no	2,300	6.2	3.0	7.2	3.5	1.0	0.5	1.0	0.11	—	—	1.5	0.06
16	no	2,120	5.8	2.8	6.8	3.3	1.0	0.5	0.8	0.10	—	—	1.3	0.06
17	half/half	1,980	3.6	1.5	4.6	1.9	1.0	0.4	0	—	—	—	0	0
18	half/half	1,840	—	—	7.6	3.1	—	—	—	—	—	—	1.1	0.07

^a To obtain seawater permeability, Q_p , the seawater absorbed by the concrete was estimated as 2.0 cu ft and was subtracted from the total seawater intake, Q .

Figure 12. Total seawater intake of concrete spheres.

and for another sphere (specimen CWL-6) at a simulated depth of 3,760 feet it was:

$$Q_p = 0.32 \log_{10} T - 0.01 \quad (3)$$

where T is time (days).

Figure 13 shows a comparison between D'Arcy's equation, Equation 1, using $K_c = 0.13 \times 10^{-12}$ ft/sec and the empirical equations, Equations 2 and 3. Data from the ocean spheres are shown to be bracketed by the D'Arcy and empirical semi-log relations. D'Arcy's

relation assumes a constant rate of permeability, whereas the extrapolation of the empirical semi-log relation assumes a decreasing rate with time. It is not apparent at this time which approach defines the permeability behavior of the concrete spheres. Additional data from inspections are required.

Sphere 8 was found intact but sitting on the seafloor after 431 days. A total seawater intake of 15.3 cu ft or more was required to overcome the positive buoyancy of the sphere. This quantity of seawater was three to four times that of the other

Table 6. Permeability Data (After Haynes and Kahn [8])

Specimen No.	Simulated Depth (ft)	Time (days)	Permeability, Q_p (cu ft)	D'Arcy's Permeability Coefficient, K_c (ft/sec $\times 10^{-12}$)
CWL-9A	2,520	21	0.34	0.16
CWL-6	3,760	42	0.52	0.10

NOTE: Spheres started the test having the concrete in a wet condition. The procedure for obtaining wet-concrete walls was to place an uncoated sphere on the bottom of the pressure vessel and allow the seawater to fill the inside of the sphere, and then apply hydrostatic pressure. The pressure was maintained usually for 7 days at 500 psi or until the pressure became constant and showed no decrease, thus indicating that the voids of more significant size were filled with water.

spheres, so it was evident that Sphere 8 leaked. Experience in fabricating concrete spheres has shown that periodically a specimen leaked at a concrete-epoxy joint.

SUMMARY

Of the original eighteen spheres emplaced at depths between 1,840 and 5,075 ft, fifteen spheres have been inspected at least once. Of the spheres that were inspected, the one at greatest depth was at 4,185 feet, and was performing well after 431 days. Two spheres have imploded; one sphere imploded during emplacement to the depth of 4,330 feet and the other sphere imploded during the time interval of 1 to 431 days at a depth of 3,725 feet.

The quantity of seawater that had permeated through the concrete walls was about 0.8 cu ft for the coated spheres (waterproofed concrete) and 1.6 cu ft for the uncoated spheres (non-waterproofed concrete).

D'Arcy's permeability coefficient, K_c , was on the average 0.02×10^{-12} ft/sec for the coated spheres and 0.06×10^{-12} ft/sec for the uncoated spheres between the time interval of 0 to 431 days on the seafloor. These K_c values were less than the K_c value of 0.13×10^{-12} ft/sec obtained from pressure vessel tests on similar uncoated spheres for time intervals up to 42 days [8].

The concrete spheres are to remain in the ocean through 1981 with periodic inspections to determine implosion and permeability data.

ACKNOWLEDGMENTS

The author wishes to acknowledge the assistance of Mr. L. F. Kahn during the planning and fabrication stages, of Mr. N. D. Albertsen in emplacing the spheres in the ocean, of Mr. P. C. Zubiate as senior project technician, and of Mr. D. W. Widmayer in fabricating the spheres.

REFERENCES

1. Naval Civil Engineering Laboratory. Technical Report R-517: Behavior of spherical concrete hulls under hydrostatic loading, pt. 1. Exploratory investigation, by J. D. Stachiw and K. O. Gray. Port Hueneme, CA, Mar. 1967. (AD649290)
- 2.———. Technical Report R-547: Behavior of spherical concrete hulls under hydrostatic loading, pt. 2. Effect of penetrations, by J. D. Stachiw. Port Hueneme, CA, Oct 1967. (AD661187)
- 3.———. Technical Report R-588: Behavior of spherical concrete hulls under hydrostatic loading, pt. 3. Relationship between thickness-to-diameter ratio and critical pressures, strains, and water permeation rates, by J. D. Stachiw and K. Mack. Port Hueneme, CA, Jun. 1968. (AD835492L)
- 4.———. Technical Report R-679: Failure of thick-walled concrete spheres subjected to hydrostatic loading, by H. H. Haynes and R. A. Hoofnagle. Port Hueneme, CA, May 1970. (AD708011)
- 5.———. Technical Report R-696: Influence of length-to-diameter ratio on behavior of concrete cylindrical hulls under hydrostatic loading, by H. H. Haynes and R. J. Ross. Port Hueneme, CA, Sep. 1970. (AD713088)
- 6.———. Technical Report R-735: Influence of stiff equatorial rings on concrete spherical hulls subjected to hydrostatic loading, by L. F. Kahn and J. D. Stachiw, Port Hueneme, CA, Aug. 1971. (AD731352)
- 7.———. Technical Report R-740: Influence of end-closure stiffness on behavior of concrete cylindrical hulls subjected to hydrostatic loading, by L. F. Kahn. Port Hueneme, CA, Oct. 1971. (AD732363)
- 8.———. Technical Report R-774: Behavior of 66-inch concrete spheres under short and long term hydrostatic loading, by H. H. Haynes and L. F. Kahn. Port Hueneme, CA, Sep. 1972. (AD748584)
- 9.———. Technical Report R-785: Hydrostatic loading of concrete spherical hulls reinforced with steel liners, by H. H. Haynes, G. L. Page and R. J. Ross. Port Hueneme, CA, Apr. 1973. (AD 759684)
- 10.———. Technical Report R-790: Influence of compressive strength and wall thickness on behavior of concrete cylindrical hulls under hydrostatic loading, by N. D. Albertsen. Port Hueneme, CA. June 1973.
- 11.———. Technical Note N-——: Influence of steel bar reinforcement on the behavior of concrete spherical hulls, by N. D. Albertsen. Port Hueneme, CA. (To be published.)
12. Informal correspondence, J. Baker, Graduate student, University of California, Berkeley, CA, letter of 8 February 1973, to H. H. Haynes, Naval Civil Engineering Laboratory, Port Hueneme, CA.
13. Amelyanovich, K. K., Verbitsky, V. D., and Sintsov, G. M., "Results of research into performance of concrete and reinforced concrete members under high pressure head," in *Proceedings of Federation Internationale de la Precontrainte (FIP) Symposium on Concrete Sea Structures, Tbilisi, USSR, Sep. 1972.* [Translated London, 1972.]

Appendix A

CONCRETE MATERIALS

The mix design for the concrete is given in Table A-1. Transit-mix trucks delivered the concrete, and final determination of water content was based on workability. Table A-2 gives the properties of the fresh concrete; average values were (1) water-to-cement ratio of 0.40, (2) slump of 1-1/2 inches, (3) air content of 2.4 percent by volume, and (4) unit weight of 145.2 lb/cu ft.

Compressive strength of the concrete at age 28 days (Table A-2) averaged 7,660 psi for the fog-room-cured specimens and 7,690 psi for the on-land field-cured specimens (moist-cured in wet burlap and wrapped in plastic for first 28 days). The compressive strength of the concrete at ages varying from 45 to 174 days was obtained prior to emplacing the spheres in the ocean (Table A-2). These strengths were used to calculate the short-term implosion pressure of the spheres (the compressive strength of the weaker hemisphere was used) so that projected emplacement depths could be calculated. For the uncoated spheres, the control cylinders were saturated with seawater prior to testing. The method of saturation was to place the specimens in a pressure vessel and apply 500 psi pressure for 7 days. The strength of saturated concrete has been found to be 10% lower than room-dry concrete [8]. The coating was assumed to maintain the concrete in a dry condition, so the control cylinders were tested in a dry condition.

Table A-3 is a copy of a typical mill test report on the portland cement used by the transit-mix supplier, Southern Pacific Milling, during the fabrication of the hemispheres. All of the cement meets ASTM specification C-150-70, Type II, Low Alkali, Portland Cement.

X-ray diffraction patterns for three concrete blocks, W-15, W-39, and W-41, were obtained (Figures A-1 through A-3) for documentation of the chemical composition of the concrete at the early stages of the test program. At the end of the test program, which could be many years away, samples of concrete can be analyzed to determine whether or not the concrete has been attacked by the sulphates in seawater. Table A-4 gives the diffraction angle (2θ) of the expected intensity peaks for concrete attacked and unattacked by sulphates in seawater [12].

Table A-1. Concrete Mix Design

Portland cement, Type II, low-alkali
 Santa Clara River aggregate
 Water-to-cement ratio = 0.41
 Sand-to-cement ratio = 1.85
 Coarse aggregate-to-cement ratio = 2.28
 Water-reducing admixture = 2 oz/slack of Plastiment

Material	Aggregate Gradation		
	Sieve Size Designation	Percentage Retained	
		Individual	Cumulative
Sand	3/8 inch	0	0
	no. 4	2	2
	no. 8	11	13
	no. 16	17	30
	no. 30	28	58
	no. 50	28	86
	no. 100	11	97
	pan	3	100
Coarse aggregate	3/4 inch	0	0
	3/8 inch	70	70
	no. 4	30	100

Table A-2. Concrete Control Cylinder Data

Sphere No.	Hemisphere No. ^a	Characteristics of Fresh Concrete Cylinders				Compressive Strength, f'_c at 28 Days (psi)			Age, Condition, and Compressive Strength, f'_c Prior to Ocean Emplacement	
		Water-to-Cement Ratio	Slump (in.)	Air Content by Volume (%)	Density (lb/cu ft)	Wrapped Wet Burlap and Plastic ^b	Fog Room ^b	Age (days)	Condition of Concrete ^c	f'_c (psi)
1	W-4	0.42	3/4	2.3	146.0	7,300	8,520	174	dry	8,940
	W-35	0.41	1-1/4	2.2	145.2	8,070	8,070	65	dry	9,360
2	W-8	0.38	1-1/4	2.2	146.4	8,050	8,250	164	dry	9,950
	W-7	0.38	1-1/2	2.2	145.2	7,590	7,940	162	dry	8,970
3	W-16 ^d	0.38	1-3/4	2.1	145.1	7,940	8,400	132	dry	9,650
	W-15	0.38	1-1/4	2.3	147.8	7,260	8,520	134	dry	8,840
4	W-6	0.41	1/4	5.8	138.3	8,470	8,760	170	wet	8,320
	W-5	0.43	1-1/4	2.7	146.4	7,310	8,050	172	wet	7,600
5	W-10	0.44	1-1/4	2.5	144.9	7,210	7,730	156	wet	8,090
	W-9	0.40	1-1/4	2.1	146.1	7,620	8,240	158	wet	7,690
6	W-14	0.42	1-1/4	2.2	147.0	8,100	8,580	143	wet	8,510
	W-13	0.41	1-1/2	2.6	148.0	7,960	8,060	144	wet	8,370
7	W-20	0.39	1-1/2	2.7	143.9	7,720	7,660	117	dry	9,530
	W-17	0.36	2	2.1	147.2	7,370	7,750	126	dry	9,480
8	W-22	0.41	1-1/4	2.5	144.1	7,690	7,520	111	dry	9,030
	W-19	0.38	1-3/4	2.2	145.2	7,940	8,410	119	dry	9,380
9	W-28	0.42	1-3/4	1.6	147.0	6,970	6,920	94	wet	7,820
	W-25	0.38	1-3/4	2.1	145.2	7,890	8,070	104	wet	8,740
10	W-30	0.39	1-1/2	2.1	145.6	7,950	8,190	88	wet	8,560
	W-27	0.42	1-1/4	2.3	146.2	7,620	7,900	97	wet	8,330
11	W-24	0.38	1-1/2	2.1	145.2	7,670	7,540	103	dry	9,820
	W-21	0.36	1-3/4	2.4	146.0	7,670	7,720	113	dry	9,190
12	W-32	0.40	1-1/2	2.4	145.8	7,510	7,570	80	wet	8,390
	W-29	0.40	1-3/4	1.7	146.0	7,030	7,240	89	wet	7,430
13	W-26	0.39	1-1/4	2.3	145.0	7,990	8,070	98	dry	10,210
	W-23	0.39	1-1/4	2.7	143.9	7,860	7,640	105	dry	9,370

continued

Table A-2. Continued

Sphere No.	Hemisphere No. ^a	Characteristics of Fresh Concrete Cylinders				Compressive Strength, f'_c , at 28 Days (psi)		Age, Condition, and Compressive Strength, f'_c , Prior to Ocean Emplacement	
		Water-to-Cement Ratio	Slump (in.)	Air Content by Volume (%)	Density (lb/cu ft)	Wrapped Wet Burlap and Plastic ^b	Fog Room ^b	Age (days)	Condition of Concrete ^c
14	W-12 ^d	0.42	1-1/4	3.2	136.6	6,730	6,990	144	dry
	W-11	0.43	3/4	—	—	7,440	7,550	148	dry
15	W-34	0.37	1-1/2	2.1	145.6	7,800	8,170	74	wet
	W-31	0.38	1-1/4	2.0	146.4	7,880	7,810	82	wet
16	W-36	0.38	1-1/2	2.3	145.4	7,520	7,220	67	wet
	W-33	0.41	1-1/2	2.4	145.8	8,050	7,930	75	wet
17	W-39	—	1-1/4	2.1	145.4	7,690	8,050	51	dry
	W-40	—	1-1/2	2.0	145.8	7,740	7,730	52	wet
18	W-41	—	1-1/2	2.6	144.3	7,600	8,620	48	dry
	W-42	—	1-1/2	2.5	144.5	7,810	7,970	45	wet

^a Hemisphere number listed first refers to the top hemisphere of the sphere.^b Average of three 6 x 12-in.-long control cylinders.^c Dry refers to cylinders from on-land field conditions.^d Wet refers to cylinders placed in seawater under 500 psi for 7 days.^e Some expanded shale aggregate found in cylinder.

Table A-3. Copy of Mill Test Report on Cement

PACIFIC WESTERN INDUSTRIES, INC.
LOS ROBLES CEMENT DIVISION

POST OFFICE BOX 1247 • (805)248-6733
 LEBEC, CALIFORNIA 93243

MILL TEST REPORT

We certify that 17,982 bbls. of LOS ROBLES Portland Cement in
 Silo or Lot No. 1-802 has the following chemical and physical characteristics
 as tested in our plant laboratory:

CHEMICAL ANALYSIS:

Silicon Dioxide, SiO ₂ . . .	<u>22.28</u>	%
Aluminum Oxide, Al ₂ O ₃ . . .	<u>4.62</u>	%
Ferric Oxide, Fe ₂ O ₃ . . .	<u>3.04</u>	%
Calcium Oxide, CaO . . .	<u>64.24</u>	%
Magnesium Oxide, MgO . . .	<u>1.46</u>	%
Sulphur Trioxide, SO ₃ . . .	<u>2.73</u>	%
Loss on Ignition	<u>1.38</u>	%
Insoluble	<u>0.05</u>	%
Alkalies, Comb. as Na ₂ O . . .	<u>0.42</u>	%

POTENTIAL COMPOUNDS:

3 CaO.SiO ₂	<u>49.0</u>	%
2 CaO.SiO ₂	<u>26.9</u>	%
3 CaO.Al ₂ O ₃	<u>7.1</u>	%
4 CaO.Al ₂ O ₃ .Fe ₂ O ₃	<u>9.2</u>	%

FINENESS:

Blaine, Sq. Cm. per Gram	3476
Wagner, Sq. Cm. per Gram	

SOUNDNESS:

Autoclave, Percent Expansion	.000
------------------------------	------

TIME OF SETTING:

Vicat	1 hrs.	45 min.
Gilmore, Initial Set	2 hrs.	50 min.
Final Set	4 hrs.	30 min.

COMPRESSIVE STRENGTH:

1 day	1552	psi
3 days	2838	psi
7 days	4411	psi
28 days	6802	psi

THIS CEMENT MEETS OR EXCEEDS THE FOLLOWING DESCRIBED SPECIFICATIONS:

ASTM: C-150-70 Type II Low Alkali

FEDERAL: SS-C-192g Type II Low Alkali

CALIFORNIA: State Div. of Hwys. Std. Spec. 90-2.01 Mod. Type II Low Alkali

OTHER: _____

MAIN OFFICE:

3810 Wilshire Boulevard
 Los Angeles, California 90005
 (213) 381-3181

Pacific Western Industries, Inc.

BY: _____ 4-2-71
 CHIEF CHEMIST DATE

Table A-4. Expected Intensity Peaks [12] From X-Ray Diffraction Analysis of Concrete Attacked and Unattacked by Seawater

Diffraction Angle (2θ) at Intensity Peak (deg)	Material	Remarks	
Concrete Attacked by Sulfates in Seawater			
9.1 15.8	Ettringite, $3\text{CaOAl}_2\text{O}_3 \cdot 3\text{CaSO}_4 \cdot 32\text{H}_2\text{O}$	May not be present.	
11.2	Hydrocalumite, $\text{Ca}_{16}\text{Al}_{18}(\text{OH})_{54}\text{CO}_3 \cdot 21\text{H}_2\text{O}$		
11.7	Gypsum, $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$		Very soluble, may not be present.
29.4	Calcite, CaCO_3		Due to carbonation.
26.2 27.2	Aragonite, CaCO_3		Formed at cold temperatures, may not be present.
Concrete Unattacked			
18.1 34.1	Lime, $\text{Ca}(\text{OH})_2$	Created from hydrated cement.	
broad peak ~28-33	Tobermorite gel	Created from hydrated cement.	
32.3 32.7 33.1	C_3S C_3S and C_2S C_3A	Traces of unhydrated cement, usually hard to see in older concrete.	
29.4	Calcite, CaCO_3	Due to carbonation.	
10.5 20.9 26.6 ^a 27.8	Aggregates	Some of the larger peaks from the aggregate.	

^a Quartz aggregate.

Figure A-1. X-ray diffraction pattern for concrete from W-15 control block.

Figure A-2. X-ray diffraction pattern for concrete from W-39 control block.

Figure A-3. X-ray diffraction pattern for concrete from W-41 control block.

Appendix B

SOIL PROPERTIES

Table B-1. Soil Data

(Core specimen obtained at 4,100 feet near Sphere 5; core diameter was 2.75 inches.)

Item	Properties of Soil Sample From Core by Intervals		
	0-3 In.	6-9 In.	13-16 In.
Bulk wet density (pcf)	90.64	94.53	94.20
Water content (%)	82.69	83.39	85.54
Vane shear strength (psi)	0.296	1.074	1.431
Remolded shear strength (psi)	0.037	0.394	0.566
Sensitivity	8.0	2.7	2.5
Liquid limit	81.7	91.0	112.3
Plastic limit	42.3	39.9	42.5
Plasticity index	39.4	51.1	69.8
Specific gravity	2.63	2.57	2.61
Unified soil classification	MH	MH	CH
Type of soil	silt	silt	clay-silt

Appendix C

COMPRESSIVE STRENGTH OF CONCRETE FOR SPHERE 3

Even though Sphere 3 imploded on descent to the seafloor, the control block of concrete was not retrieved until 340 days later. This control block was fabricated of the same concrete as one of the sphere's hemispheres, W-16. This concrete experienced a history of 172 days of on-land field curing and 340 days of in-ocean field curing.

The other hemisphere, W-15, had a corresponding control block that was continuously stored out-of-doors; hence, this concrete underwent a continuous 514 days of on-land field curing. Simultaneously, three 6 x 12-inch-long cylinders for both hemispheres underwent continuous fog room curing.

The compressive strengths for the concrete are shown in Table C-1 and Figure C-1. The fog-cured concrete increased 23 percent in average strength, from 8,460 to 10,420 psi. The on-land field-cured concrete leveled off in strength at an average of 8,650 psi after 134 days. The in-ocean field-cured concrete decreased in strength from an average of 9,650 psi after 132 days of on-land curing to an average of 7,600 psi after 340 days in the ocean; this was a 21 percent decrease in strength. Wetting of the dry concrete would account for 10 percent of the decrease [8]; perhaps under the long-term hydrostatic pressure the total decrease in strength was due to saturation of the concrete. Previous work by Russians [13] showed a decrease in compressive strength of 28 percent due to saturating dry concrete under high hydrostatic pressure; however, the test procedure used to obtain the saturated concrete was not discussed.

Concrete from block W-16 was analyzed by x-ray diffraction techniques. It was found that the concrete was not attacked by the seawater.

Table C-1. Control Cylinder Data for Sphere 3

Hemisphere	Curing Condition	Total Age (days)	Saturated With Seawater Prior to Test	Number of Control Specimens	Compressive Strength, f'_c (psi)	Coefficient of Variation (%)
W-15	Fog Room	28	no	3	8,520	—
	Field ^a	28	no	3	7,260	—
	With Hemisphere ^a	134	no	3	8,840	—
	Fog Room	514	no	3	10,470	3.9
	Field at CEL ^{a, b}	514	no	4	8,650	3.7
W-16	Fog Room	28	no	3	8,400	—
	Field ^a	28	no	3	7,940	—
	With Hemisphere ^a	132	no	3	9,650	—
	Fog Room	512	no	3	10,360	1.5
	In ocean ^{a, b} (at 4,400 ft for 341 days)	512	yes	4	7,600	4.0

^a First 28 days: moist-cured in wet burlap wrapped in plastic sheeting.

^b 6 x 12-in.-long cylinders cored from block 18 x 18 x 14 inches.

Figure C-1. Compressive strength of concrete for Sphere 3.

Appendix D

CALCULATION OF SEAWATER INTAKE

The method used to calculate the total quantity of seawater intake by the spheres depends on obtaining the change in number of chain links suspended off the seafloor by a sphere. The reduction in number of links is converted into quantity of seawater intake, Q . The accuracy of determining Q is dependent on several approximations.

One approximation is the criterion by which the submersible operators counted the chain links. They counted only whole links; or, in other words, the bottom-most link counted was the one in a vertical position.

Another approximation is estimating the original number of links suspended off the seafloor when the spheres had dry-concrete walls. The associated calculations are shown below, in part, and are completed in Table D-1.

Buoyancy of Hull

Dimensions $D_o = 65.886$ inches and $D_i = 57.640$ inches

Weight of Displaced Seawater, W_D

$W_D = 64$ pcf (86.64 cu ft) = 5,545 lb

Weight of Concrete Sphere, W_C

$W_C = 145.2$ pcf (28.625 cu ft) = 4,156 lb

Positive Buoyancy = 1,389 lb for bare concrete hull

In-Water Weight of Components on Spheres

5/8-inch chain	67 lb
Wet-concrete control block	220 lb
Steel components	40 lb
Titanium components	8 lb
Load on Spheres 7-16 (also common load to other spheres)	335 lb
Clock (estimated in air weight)	20 lb
Batteries (estimated in air weight)	40 lb
Common load	+335 lb
Load on Spheres 1-6	395 lb
Steel bar reinforcement (in-water weight)	150 lb
Common load	+335 lb
Load on Spheres 17 and 18	485 lb

Column D in Table D-1 was another approximation. This was the apparent weight gain of the system due to the change in volume of the sphere under load. Using data from Reference 8, it was assumed that the maximum long-term strain for the spheres at greatest depths was 2,500 $\mu\text{in./in.}$ This strain resulted in a

change in volume sufficient to reduce the buoyancy by 40 pounds. For the spheres in shallower water, a proportional buoyancy adjustment was made.

It was estimated that the maximum error in the net positive buoyancy values was ± 50 pounds. In terms of chain links (2-1/4-inch chain), the error was ± 1.5 links; or in terms of seawater intake, the error was ± 0.8 cu ft.

The error associated with permeability reading between inspections is ± 20 pounds, or ± 0.3 cu ft.

Table D-1. Calculation of Number of Links Off Seafloor at Zero Days

Sphere No.	A Positive Buoyancy of Concrete Hull (lb)	B Weight ^a of Components on Hull (lb)	C Weight ^a of Shackles (lb)	D Apparent Weight Gain (lb) ^b	E = A - [B + C + D] Net Positive Buoyancy (lb)	F Chain Size (in.)	G Weight ^a of Each Chain Link (lb/link)	H = E/G Number of Links Off Seafloor
1	1,389	395	28	40	926	2-1/4	31.2	29.7
2	1,389	395	28	40	926	2-1/4	31.2	29.7
3	1,389	395	42	35	917	2-1/4	31.2	29.4
4	1,389	395	42	35	917	2-1/4	31.2	29.4
5	1,389	395	42	30	922	2-1/4	31.2	29.6
6	1,389	395	42	30	922	2-1/4	31.2	29.6
7	1,389	335	42	30	982	2-1/4	31.2	31.5
8	1,389	335	42	30	982	2-1/4	31.2	31.5
9	1,389	335	42	25	987	2-1/4	31.2	31.6
10	1,389	335	42	25	987	2-1/4	31.2	31.6
11	1,389	335	42	25	987	2-1/4	26.0	38.0
12	1,389	335	28	25	1,001	2-1/4	31.2	32.1
13	1,389	335	28	25	1,001	2-1/4	31.2	32.1
14	1,389	335	28	20	1,006	2	20.8	48.4
15	1,389	335	28	20	1,006	2-1/4	31.2	32.2
16	1,389	335	42	20	992	2-1/4	31.2	31.8
17	1,389	485	42	15	847	2-1/8	26.0	32.6
18	1,389	485	42	15	847	2-1/8	26.0	32.6

^a In-water weight.^b Due to change in volume of sphere under load.

LIST OF SYMBOLS

A	Exterior surface area, cu ft
D_i	Inner diameter of concrete sphere, in.
D_o	Outer diameter of concrete sphere, in.
f'_c	Uniaxial compressive strength of concrete, psi
h	Depth (or pressure head), ft
K_c	Permeability coefficient, ft/sec
P_{im}	Short-term implosion pressure, psi
P_s	Sustained pressure, psi
Q	Total quantity of seawater intake, cu ft
Q_p	Quantity of seawater permeating wall of sphere, cu ft
T	Time, sec, hr, days
t	Wall thickness, ft, in.
W_C	Weight of concrete sphere, lb
W_D	Weight of displaced seawater, lb

DISTRIBUTION LIST

SNDL Code	No. of Activities	Total Copies	
—	1	12	Defense Documentation Center
FKAIC	1	10	Naval Facilities Engineering Command
FKNI	6	6	NAVFAC Engineering Field Divisions
FKN5	9	9	Public Works Centers
FA25	1	1	Public Works Center
—	9	9	RDT&E Liaison Officers at NAVFAC Engineering Field Divisions and Construction Battalion Centers
—	209	209	CEL Special Distribution List No. 11 for persons and activities interested in reports on Ocean Engineering
Bernard Willey (Code 385) * Boston Naval Shipyard Boston, MA 02129			Public Works Officer Naval Security Group Activity Winter Harbor, ME 04693
			Public Works Officer U. S. Naval Facility FPO New York 09552
LCDR David A. Cacchione, USN Office of Naval Research, BROFF 495 Summer Street Boston, MA 02210			Public Works Department Box 400 Naval Submarine Base, New London Groton, CT 06340
			Staff Civil Engineer U. S. Naval Air Station Box 35-D FPO New York 09593
Commanding Officer (Code 200) Navy Public Works Center Naval Base Newport, RI 02840			LCDR T. A. Long, Jr., CEC, USN Naval Submarine Base, New London Groton, CT 06340
			RDT&E Liaison Officer Code 102 Northern Division Naval Facilities Engineering Command Philadelphia, PA 19112
President Naval War College Code 22 Newport, RI 02840			Commanding General U. S. Army Electronics Command Attn AMSEL-GG-TD Fort Monmouth, NJ 07703
			Public Works Officer Naval Facility Lewes, DE 19958
Mr. S. Milligan SB 322 Naval Underwater Systems Center Newport, RI 02844			Engineering Director Code 092 Naval Ammunition Depot, Earle Colts Neck, NJ 07722
			Mr. R. B. Allnutt Code 1706 Naval Ship Research & Dev. Center Bethesda, MD 20034
Commander 21st Naval Construction Regiment Davisville, RI 02854			Plastics Technical Evaluation Center SMUPA-VP3 Picatinny Arsenal Dover, NJ 07801
			Mr. M. A. Krenzke Code 172 - Submarine Division Naval Ship Research & Dev. Center Bethesda, MD 20034
Commanding Officer CBC Technical Library Naval Construction Battalion Center Davisville, RI 02854 (2 copies)			Commanding Officer Amphibious Construction Battalion TWO FPO New York 09501
			William F. Gerhold National Bureau of Standards Corrosion Section Washington, DC 20234
Library U. S. Army Cold Regions Research & Eng. Lab. P. O. Box 282 Hanover, NH 03755			LT Ronald A. Milner, CEC, USN U. S. Naval Station Box 9 FPO New York 09540
			A. Malliar Maritime Administration Office of Ship Construction Washington, DC 20235

* All addressees receive one copy unless otherwise indicated.

Chief of Engineers U. S. Army DAEN-MCE-D Washington, DC 20314	Commandant (M-2/USP/83) U. S. Coast Guard 400 SW 7th Street Washington, DC 20590	LCDR G. E. Shank, CEC, USN Office of Naval Research Ocean Technology Program 800 North Quincy Street Arlington, VA 22217
Benj. R. Petrie, Jr. Op-987TB, Director RDT&E Room 4B514, Pentagon Washington, DC 20350	Commander Naval Ship Engineering Center Code 6136 Prince Georges Center Hyattsville, MD 20782	Dr Nicholas Perrone Code 439 Office of Naval Research 800 North Quincy Street Arlington, VA 22217
ENS James F. Morrow, CEC, USN Office of Comptroller of the Navy Navy Department Washington, DC 20350	Commander Naval Ship Engineering Center Code 6162 Prince Georges Center Hyattsville, MD 20782	Dr Alexander Malahoff Code 483 Office of Naval Research 800 North Quincy Street Arlington, VA 22217
Commander Naval Supply Systems Command Headquarters SUP 0423 Washington, DC 20360	Technical Library Naval Ship Engineering Center 622 Center Bldg Prince Georges Center Hyattsville, MD 20782	LCDR J.H. Osborn, CEC, USN Chief of Naval Material (MAT 03414) c/o Oceanographer of the Navy 200 Stovall Street Alexandria, VA 22332
Technical Library, Ships 2052 Naval Ship Systems Command National Center No. 3 Washington, DC 20362	Mr. John B. Alfors Naval Ship Engineering Center Code 6101E Prince Georges Center Hyattsville, MD 20782	Oceanographer of the Navy Attn: Code N712 200 Stovall Street Alexandria, VA 22332
Commander Naval Ship Systems Command Code 00C Washington, DC 20362	Chief, Marine & Earth Sciences Library National Oceanic & Atmospheric Admin. Dept. of Commerce Rockville, MD 20852	CAPT Pharo A. Phelps, CEC, USN Naval Facilities Engineering Command 200 Stovall Street Alexandria, VA 22332
Chief Bureau of Medicine & Surgery Research Department Navy Department Washington, DC 20372	M. E. Ringenbach Engineering Development Lab (C61) National Oceanic & Atmospheric Admin. National Ocean Survey Rockville, MD 20852	Dr. Michael Yachnis Code 048 Naval Facilities Engineering Command 200 Stovall Street Alexandria, VA 22332
U. S. Naval Oceanographic Office Library - Code 3600 Washington, DC 20373	Mr. H. A. Perry Naval Ordnance Laboratory, White Oak Silver Spring, MD 20910	CDR G.H. Gans, Jr., CEC, USN Code 042 Naval Facilities Engineering Command 200 Stovall Street Alexandria, VA 22332
John DePalma U. S. Naval Oceanographic Office Code 9233 Washington, DC 20373	LCDR Robert D. Smart, CEC, USN Naval System Engineering Dept U. S. Naval Academy Annapolis, MD 21402	Commander Code 0436B Naval Facilities Engineering Command 200 Stovall Street Alexandria, VA 22332
Director Code 2627 Naval Research Laboratory Washington, DC 20375	Director Division of Engineering & Weapons U. S. Naval Academy Annapolis, MD 21402	CDR Walter J. Eager, CEC, USN Code PC-2 Naval Facilities Engineering Command 200 Stovall Street Alexandria, VA 22332
Mr. J. P. Walsh Naval Research Laboratory Code 8400 Washington, DC 20375	Dr Neil T. Monney Naval Systems Engineering Dept U. S. Naval Academy Annapolis, MD 21402	Mr. C.R. Odden Code PC-2 Naval Facilities Engineering Command 200 Stovall Street Alexandria, VA 22332
Mr. J. J. Gennari Naval Research Laboratory Code 8410 Washington, DC 20375	Mr. D. H. Kallas Annapolis Laboratory Naval Ship Research & Dev. Center Annapolis, MD 21402	Commanding Officer Navy Public Works Center Norfolk, VA 23511
Director of Navy Laboratories Room 300, Crystal Plaza Bldg 5 Department of the Navy Washington, DC 20376	Library, Code 5642 Annapolis Laboratory Naval Ship Research & Dev. Center Annapolis, MD 21402	RDT&E Liaison Officer Code 09P2 Atlantic Division Naval Facilities Engineering Command Norfolk, VA 23511 (2 copies)
Commanding Officer Chesapeake Division - Code 03 Naval Facilities Engineering Command Washington Navy Yard Washington, DC 20390	Commanding Officer U. S. Army Mobility Equip. R&D Center Attn: SMEFB-HPC (Mr. Cevasco) Fort Belvoir, VA 22060	Staff Civil Engineer Commander Service Force U. S. Atlantic Fleet Norfolk, VA 23511
CDR L. K. Donovan, CEC, USN Chesapeake Division Naval Facilities Engineering Command Washington Navy Yard Washington, DC 20390	U.S. Army Coastal Eng. Research Center Kingman Building Fort Belvoir, VA 22060	Director Amphibious Warfare Board Naval Amphibious Base, Little Creek Norfolk, VA 23521
Commandant Naval District Washington Public Works Department-Code 412 Washington, DC 20390	U.S. Army Coastal Eng. Research Center R.A. Jachowski Kingman Building Fort Belvoir, VA 22060	Commandant U.S. Army Logistics Management Center Attn: DLSIE Fort Lee, VA 23801
Naval Security Engineering Facility Technical Library 3801 Nebraska Avenue, NW Washington, DC 20390	Facilities Officer Code 108 Office of Naval Research 800 North Quincy Street Arlington, VA 22217	Public Works Officer Naval Hospital Camp Lejeune, NC 28542

RD&E Liaison Officer
Southern Division - Code 90
Naval Facilities Engineering Command
P. O. Box 10068
Charleston, SC 29411

LCDR G. W. Callender, Jr., CEC, USN
NROTC Unit
Georgia Institute of Technology
Atlanta, GA 30332

Public Works Officer
Naval Coastal Systems Laboratory
Panama City, FL 32401

Mr. R. E. Elliott
Code 710
Naval Coastal Systems Laboratory
Panama City, FL 32401

Library Branch
Army Eng. Waterways Experiment Station
Vicksburg, MS 39180

Army Construction Eng. Research Lab.
ATTN Library
P.O. Box 4005
Champaign, IL 61820

Commanding Officer - Eng. Div.
MRD - Corps of Engineers
Department of the Army
P. O. Box 103, Downtown Station
Omaha, NE 68101

Public Works Officer
Naval Air Station, New Orleans
Belle Chasse, LA 70037

Public Works Officer
Naval Ammunition Depot
McAlester, OK 74501

LT H. S. Stevenson, CEC, USN
Texas A & M University
2304 Truman Street
Bryan, TX 77801

Dr. Arthur R. Laufer
Office of Naval Research, BROFF
1030 East Green Street
Pasadena, CA 91106

Officer in Charge
Pasadena Lab. - Naval Undersea Center
Attn Technical Library
3202 E. Foothill Blvd
Pasadena, CA 91107

Public Works Officer
Marine Corps Base
Camp Pendleton, CA 92055

Mr. H. R. Talkington
Code 65
Naval Undersea Center
San Diego, CA 92132

Dr. J. D. Stachiw
Code 6505
Naval Undersea Center
San Diego, CA 92132

Mr. R. E. Jones
Code 65402
Naval Undersea Center
San Diego, CA 92132

Technical Library
Code 1311
Naval Undersea Center
San Diego, CA 92132

Director
San Diego Branch
Western Division
Naval Facilities Engineering Command
San Diego, CA 92132

Public Works Officer
Code 75
Naval Undersea Center
San Diego, CA 92132

Public Works Officer
Naval Air Station
North Island
San Diego, CA 92135

Staff Civil Engineer
Naval Station
San Diego, CA 92136

Commanding Officer
Navy Public Works Center
Naval Base
San Diego, CA 92136

Commanding Officer
Naval Missile Center
Code 5632.2, Technical Library
Point Mugu, CA 93042

Office of Patent Counsel
Code PC (Box 40)
Naval Missile Center
Point Mugu, CA 93042

Librarian, Code 9215
Construction Equipment Department
Naval Construction Battalion Center
Port Hueneme, CA 93043

Commanding Officer
Code 155
Naval Construction Battalion Center
Port Hueneme, CA 93043

Technical Library - Code C35
Naval School
Civil Engineer Corps Officers
Bldg 44
Port Hueneme, CA 93043

Commander
31st Naval Construction Regiment
Naval Construction Battalion Center
Port Hueneme, CA 93043 (2 copies)

Commander (Code 753)
Technical Library
Naval Weapons Center
China Lake, CA 93555

Superintendent
Attn Library (Code 2124)
Naval Postgraduate School
Monterey, CA 93940

Dr Edward B. Thornton
Department of Oceanography
Naval Postgraduate School
Monterey, CA 93940

Commanding Officer
Western Division - Code 09PA
Naval Facilities Engineering Command
P. O. Box 727
San Bruno, CA 94066

Commanding Officer
Western Division - Code 04
Naval Facilities Engineering Command
P. O. Box 727
San Bruno, CA 94066

Commanding Officer
Western Division - Code 04B
Naval Facilities Engineering Command
P. O. Box 727
San Bruno, CA 94066

Commanding Officer
Western Division - Code 05
Naval Facilities Engineering Command
P. O. Box 727
San Bruno, CA 94066

Commanding Officer
Western Division - Code 20
Naval Facilities Engineering Command
P. O. Box 727
San Bruno, CA 94066

Public Works Officer
Naval Station
Treasure Island
San Francisco, CA 94130

Asst. Resident OIC of Construction
Bldg 506
Hunters Point Naval Shipyard
San Francisco, CA 94135

Public Works Department (183)
Naval Air Station
Alameda, CA 94501

Supervisor of Salvage
West Coast Representative
4300 Eastshore Highway
Emeryville, CA 94608

Director, Engineering Division
Officer in Charge of Construction
Naval Facilities Engineering Command
Contracts, Southwest Pacific
APO San Francisco 96528

Headquarters
Kwajalein Missile Range
Box 26, Attn SSC-RKLC
APO San Francisco 96555

Commanding Officer
Mobile Construction Battalion TEN
FPO San Francisco 96601

Operations Officer
Naval Construction Battalions
U. S. Pacific Fleet
FPO San Francisco 96610

Commander
Pacific Division
Naval Facilities Engineering Command
FPO San Francisco 96610

RD&E Liaison Officer
Pacific Division - Code 403
Naval Facilities Engineering Command
FPO San Francisco 96610

Mr. T. M. Ishibashi
Navy Public Works Center
Engineering Department - Code 200
FPO San Francisco 96610

Public Works Officer
U. S. Naval Station
Box 15
FPO San Francisco 96614

Mr. D. K. Moore
Hawaii Laboratory
Naval Undersea Center
FPO San Francisco 96615

Officer in Charge of Construction
Naval Facilities Engineering Command
Contracts, Marianas
FPO San Francisco 96630

LT G.D. Cullison, CEC, USN
771 Murray Dr.
Honolulu, HI 96818

Engineering Library, Code 202.5
Puget Sound Naval Shipyard
Bremerton, WA 98314

Commanding Officer
U. S. Navy Public Works Center
Box 13
FPO Seattle 98762

Commanding Officer
U.S. Naval Air Facility
Box 159
FPO Seattle 98767

Colleges, etc

Prof. W. E. Heronemus
Civil Engineering Dept
University of Massachusetts
Amherst, MA 01002

MIT Libraries
Technical Reports - Room 14 E-210
Massachusetts Institute of Technology
Cambridge, MA 02139

LCDR James W. Eckert, CEC, USN
NROTC/NAU
Massachusetts, NA 02139

Robert V. Whitman
Room 1-253
Massachusetts Institute of Technology
Cambridge, MA 02139

Mrs. A. P. Richards
Biological Sciences
William F. Clapp Labs - Battelle
Washington Street
Duxbury, MA 02332

Document Library L0-206
Woods Hole Oceanographic Institution
Woods Hole, MA 02543

Pell Marine Science Library
University of Rhode Island
Narragansett Bay Campus
Narragansett, RI 02882

Prof. R. W. Corell
Mechanical Engineering Dept.
Kingsbury Hall
University of New Hampshire
Durham, NH 03824

Kline Science Library
Kline Biology Tower, Room C-8
Yale University
New Haven, CT 06520

M. Schupack
Schupack Associates
300 Broad Street
Stamford, CT 06901

Mr. Willard J. Pierson, Jr.
University Institute of Oceanography
c/o The Bronx Community College
West 181st Street and University Ave.
Bronx, NY 10453

Reprint Custodian
Dept. of Nautical Science
U. S. Merchant Marine Academy
Kings Point, NY 11024

Dept of Civil Engineering
State University of New York
At Buffalo
Buffalo, NY 14214

Mr. R. F. Snyder
Ordnance Research Laboratory
Pennsylvania State University
State College, PA 16801

Mr. William H. Gotski
Pennsylvania State University
212 Sackett Bldg
University Park, PA 16802

Professor Adrian F. Richards
Marine Geotechnical Laboratory
Lehigh University
Bethlehem, PA 18015

Associate Librarian
Mar Science & Engineering Library
Lehigh University
15 E. Packer Avenue
Bethlehem, PA 18015

Dr Hsuan Yeh
Towne School of Civil & Mechanical Eng.
University of Pennsylvania
Philadelphia, PA 19104

Professor E. Chesson
132 DuPont Hall
Newark, DE 19711

Professor Raymond R. Fox
Nuclear Defense Design Center
School of Engineering & Applied Science
The George Washington University
Washington, DC 20006

T. W. Mermel
4540 43rd Street, NW
Washington, DC 20016

Library of Congress
Science & Technology Division
Washington, DC 20540

Research Library
Chesapeake Bay Institute
The Johns Hopkins University
Macaulay Hall
Baltimore, MD 21218

W. F. Searle, Jr.
National Academy of Engineering
808 Timber Branch Parkway
Alexandria, VA 22302

Public Documents Department
Wm. R. Perkins Library
Duke University
Durham, NC 27706

Dr Aleksandar S. Vesic
Department of Civil Engineering
Duke University
Durham, NC 27706

Dr Bruce Muga
Dept of Civil Engineering
Duke University
Durham, NC 27706

Dr Wm F. Brumund
School of Civil Engineering
Georgia Institute of Technology
Atlanta, GA 30332

Professor J. P. Hartman
Dept of Civil Eng. & Environ. Sciences
Florida Technological University
Orlando, FL 32816

Dr Charles E. Lane
Institute of Marine Science
University of Miami
Coral Gables, FL 33146

Dr R. F. McAllister
Professor of Oceanography
Florida Atlantic University
Boca Raton, FL 33432

C. R. Stephan
Florida Atlantic University
Department of Oceanography
Boca Raton, FL 33432

Lorenz G. Straub Memorial Library
St. Anthony Falls Hydraulic Laboratory
Mississippi River at 3rd Ave, SE
Minneapolis, MN 55414

Dr R. C. Jordan
Dept of Mechanical Engineering
University of Minnesota
Minneapolis, MN 55455

Library
Portland Cement Association
Research & Development Laboratories
5420 Old Orchard Road
Skokie, IL 60076

Dr N. M. Newmark
1114 Civil Engineering Bldg
University of Illinois
Urbana, IL 61801

Professor W. J. Hall
1108 Civil Engineering Bldg
University of Illinois
Urbana, IL 61801

Dr M. T. Davison
2217 Civil Engineering Bldg
University of Illinois
Urbana, IL 61801

Metz Reference Room
Civil Engineering Dept
8106 Civil Engineering Bldg
University of Illinois
Urbana, IL 61801

Acquisition Dept - Serials Section
University of Nebraska Libraries
Lincoln, NE 68508

Robert D. Tent
Undersea Services Division
Fluor Ocean Services Inc
P. O. Drawer 310
Houma, LA 70360

Department of Oceanography
Texas A & M University
College Station, TX 77843

Civil Engineering Dept
Texas A & M University
College Station, TX 77843

R. C. Dehart
Southwest Research Institute
8500 Culebra Road
San Antonio, TX 78228

Director
Institute of Marine Science
The University of Texas
Port Aransas, TX 78373

Professor M. M. Ayoub
Dept of IE
Texas Technological University
Lubbock, TX 79409

Dr Bernard C. Abbott
Allan Hancock Foundation
University of Southern California
Los Angeles, CA 90007

Director
Catalina Marine Science Center
University of Southern California
Los Angeles, CA 90007

Aerospace Corporation
Acquisitions Group
P. O. Box 92957
Los Angeles, CA 90009

Dr Young C. Kim
Dept of Civil Engineering
Calif. State University, Los Angeles
Los Angeles, CA 90032

TRW Systems
Attn P. I. Dai R1/2178
1 Space Park
Redondo Beach, CA 90278

Mr. C. C. Mow
The Rand Corporation
1700 Main Street
Santa Monica, CA 90401

Dr. Armas Laupa
The Rand Corporation
1700 Main Street
Santa Monica, CA 90406

Robert Q. Palmer
P.O. Box 7707
Long Beach, CA 90807

Dr C. V. Chelapati
Calif. State University, Long Beach
Long Beach, CA 90840

Keck Reference Room (107-78)
136 W. M. Keck Laboratory
Calif. Institute of Technology
Pasadena, CA 91109

Oceanic Library & Info. Center
P. O. Box 2369
La Jolla, CA 92037

Dr John F. Peel Brahtz
P. O. Box 825
La Jolla, CA 92037

Mr. F. Simpson
Lockheed Ocean Laboratory
3380 No. Harbor Blvd
San Diego, CA 92101

Dr F. N. Spiess
Marine Physical Laboratory of the
Scripps Institution of Oceanography
University of California
San Diego, CA 92152

Dr Victor C. Anderson
Marine Physical Laboratory of the
Scripps Institution of Oceanography
University of California
San Diego, CA 92152

J. Padilla
866 Concord Ave
Ventura, CA 93003

Manager Ocean Systems, MVJG
Lockheed Missiles & Space Co
P. O. Box 504
Sunnyvale, CA 94088

Engineering Library
Stanford University Libraries
Stanford, CA 94305

Mr. Richard G. Luthy
615 Madison Street
Albany, CA 94706

Dept of Naval Architecture
College of Engineering
University of California
Berkeley, CA 94720

Engineering Library
University of California
Berkeley, CA 94720

Michael A. Taylor
Civil Engineering Dept
College of Engineering
University of California, Davis
Davis, CA 95616

Director
Calif. Dept of Navigation & Ocean Dev.
1416 9th Street
Sacramento, CA 95814

Assoc. Professor R. A. Grace
University of Hawaii
Honolulu, HI 96822

LT G. D. Cullison, CEC, USN
771 Murray Dr
Honolulu, HI 96818

School of Oceanography
Oregon State University
Corvallis, OR 97331

Dr S. R. Murphy
University of Washington
Seattle, WA 98195

Information Officer
United Kingdom Scientific Mission
British Embassy
3100 Massachusetts Ave, NW
Washington, DC

Mrs. Ragna Adolfsson, Librarian
Cement-och Betonginstitutet
Fack 100 44 Stockholm 70
Sweden

Literature Exchange
Cement and Concrete Association
Wexham Springs
SLOUGH SL3 6PL
Bucks, England

Additions

Mr. Austin Kovacs
U.S. Army
Cold Regions Research & Eng. Lab.
P. O. Box 282
Hanover, NH 03755

Mr. John Quirk
Code 710
Naval Coastal Systems Lab.
Panama City, FL 32401

Public Works Dept.
Puget Sound Naval Shipyard
Bremerton, WA 98314

Mr. John R. Saroyan
1320 Carl Avenue
Vallejo, CA 94590

Dr. M. D. Ashton
United Kingdom Scientific Mission
British Embassy
3100 Massachusetts Avenue, NW
Washington, DC 20008

Dr. A. H. Mattcock
Department of Civil Engineering
University of Washington
Seattle, WA 98105

Meyer Steinberg
Nuclear Engineering Department
Brookhaven National Laboratory
Upton, NY 11973

Mr. J. H. Walker
Portland Cement Association
Research & Development Laboratories
5420 Old Orchard Road
Skokie, IL 60076

Mr. George Schick
Scripps Institute of Oceanography
University of California
La Jolla, CA 92038

Mr. James Snodgrass
Scripps Institute of Oceanography
University of California
La Jolla, CA 92038

Mr. Sorkin
Naval Ship Systems Command
Code 03421
Washington, DC 20362

Mr. Freund
Naval Ship Systems Command
Washington, DC 20362

George J. Peroni
985 NW 95th Street
Miami, FL 33125

Morris Schupack
Schupack & Associates
2701 Summer Street
Stamford, CT 06905

Mr. Will Foreman
Code 55 204
Naval Weapons Center
China Lake, CA 93555

Wne F. Chang
Department of Civil Engineering
University of Miami
Coral Gables, FL 33124

Adam Whitley III
SEAFERRO Inc.
3701 NW South River Drive
Miami, FL 33142

R. S. Schmid
Marine Development
Bechtel Corporation
50 Beale Street
San Francisco, CA 94111

Walter H. Price
American Cement Technical Center
P.O. Box 832
Riverside, CA 92502

Ben C. Gerwick, Jr.
Civil Engineering Department
University of California, Berkeley
Berkeley, CA 94720

Ralph Warrington
Shell Oil
P.O. Box 127
Metairie, LA 70004

Joseph F. Rynewicz
Lockheed Missile & Space Company
Depart 57-26
Bldg 150
Sunnyvale, CA 94086

Sid Beckowich
Bechtel Incorporated
50 Beale Street
San Francisco, CA 94111

James H. Jennison
Pasadena Laboratory
Naval Undersea Center
3202 E. Foothill Blvd.
Pasadena, CA 91107

CAPT E. B. Mitchell, USN
Code OOC
Naval Ship Systems Command
Washington, DC 20362

Dr. Glen Berg
Department of Civil Engineering
University of Michigan
Ann Arbor, MI 48104

Dr. Lynn Beedle
Department of Civil Engineering
Lehigh University
Bethlehem, PA 18015

Mr. Richard Thiess
Undersea Habitat Designers
87 Harris Road
Katonah, NY 10536

Mr. William Gates
Conrad Associates
14656 Oxnard Street
Van Nuys, CA 91401

Dr. J. D. Stachiw
Ocean Technology Department
Code 65
Naval Undersea Center
San Diego, CA 92132

Dr. Bryan Williams
Nuclear Branch
Gulf Radiation Technology
P.O. Box 608
San Diego, CA 92112

Mr. Larry Kahn
2143 Medford Road #2
Ann Arbor, MI 48104

Terrance J. Dahl
Oceanographic Services Inc.
5375 Overpass Road
Santa Barbara, CA 93105

Dr. R. C. Dehart
Southwest Research Institute
San Antonio, TX 78205

Joseph J. Carroll
Jaycon Engineers, Inc.
P.O. Box 26656
Houston, TX 77032

Dr. Rudolph Szilard
University of Hawaii
2565 The Mall
Honolulu, HI 96822

CAPT Jack Adams
Director of Public Services-Engineering
Department
City of Cerritos
19400 S. Pioneer Blvd.
Cerritos, CA 90701

Dr. Sidney J. Green
Manager, Applied Mechanics
Terra Tek, Inc.
915 East 4th South
Salt Lake City, UT 94102

E. V. Wright
Dravo Corp.
4800 Grant Avenue
Pittsburgh, PA 15225

Bob Oversmith
Scripps Institute of Oceanography
La Jolla, CA 92037

Dr. Gene Gorely
Manager, Structural Section
Portland Cement Association
5420 Old Orchard Road
Skokie, IL 60076

Claude Sellars, Jr.
Shell Development Corporation
3747 Bellaire Blvd.
Houston, TX 77025

Dr. Henning Ottsen (FPO-1)
Chesapeake Division
Naval Facilities Engineering
Command
Washington Navy Yard
Washington, DC 20390

Professor D. Pritz
Civil Engineering Department
University of California, Berkeley
Berkeley, CA 94720

Karl Runge
ESSO Products Research Corp.
P.O. Box 2189
Houston, TX 77001

Boris Bresler
777 Davis Hall
University of California, Berkeley
Berkeley, CA 94720

Robert Cohen
G. E.-RESO
Ocean Systems Program
3198 Chestnut Street
Philadelphia, PA 19101

Loris Gerber
The Prescon Corporation
P.O. Box 2723
Corpus Christi, TX 78403

Paul Lavoie
Engineering Design & Analysis
Laboratory
Kingsbury Hall
University of New Hampshire
Durham, NH 03824

Arvid Grant
Arvid Grant & Associates
1600 E. 4th Avenue
Olympia, WA 98506

Nils D. Olsson
The Prescon Corporation
8E Pennsylvania Avenue
Towson, MD 21128

H. Joe Meheen
Meheen Engineering Company
6464 W. 14th Avenue
Denver, CO 80214

J. Preston Mason
ESSO Production Research Company
Box 2189
Houston, TX 770001

Ron Nordgren
Shell Development Company
P.O. Box 481
Houston, TX 77001

D. M. Roy
The Pennsylvania State University
Materials Research Laboratory
University Park, PA 16802

Dr. Arthur Anderson
Concrete Technology Corporation
Port of Tacoma Road
Tacoma, WA 98421

James R. Lloyd
ESSO Production Research Company
P.O. Box 2189
Houston, TX 77001

S. Clifford Doughty
Construction Engineering Service
843 Crossway Road
Burlingame, CA 94010

Hugh Aiken
Marine Concrete Structures, Inc.
P.O. 607
Metairie, LA 70004

John S. Hollett
Global Marine Development Inc.
5959 West Century Blvd.
Los Angeles, CA 90045

C. M. Wakeman
26803 Basswood Avenue
Palos Verdes Peninsula, CA 90274

A. S. Crandon, Jr.
Dravo Corporation
Eastern Construction Division
4800 Grant Avenue
Pittsburgh, PA 15225

H. Georgi, President
AB HYDROBETONG
Fack 100 52
Stockholm 29, Sweden

Arnfinn Jensen, Captain
Norwegian Defense Construction Service
Oslo-MIL
Oslo 1, Norway

John H. Creed
Royal Norwegian Council for
Scientific & Industrial Research
Ellingsrudveien 23C
1400 Ski, Norway

Anton Brandtzaeg
Professor of Construction & Harbour
Engineering
Norwegian Technical University
Trondheim, Norway

Dr. J. Dejong
Lockheed Petroleum Services Ltd.
1 Grosvenor Square
New Westminster, B.C., Canada

Dr. R. D. Browne
Head of Materials Research
Laboratory
Taylor Woodrow Construction
Limited
345 Ruislip Road
Southall, Middlesex, England

Napolean DeMeyer
HAECON
Marathonstraat 12
9000 Gent
Belgium

Frode Hansen
Harris & Sutherland
38 Whitfield Street
London W1
United Kingdom

Franco Levi
Corso Massimo d'Azeglio 100
10126 Torino
Italy

Kurt Eriksson
VBB
Box 5038
10241 Stockholm
Sweden

Roger LaCroix
56 Faubourg Saint-Honore
75008 Paris
France

Rowland G. Morgan
Department of Civil Engineering
University of Bristol
Bristol BS6 6SX
United Kingdom

Odd E. Gjorv
Department of Civil Engineering
Technical University of Norway
7034 Trondheim
Norway

J. G. Bodhe
24-26 Dalal Street
Fort, Bombay
India

B. H. Spratt
Cement & Concrete Association
Wexham Springs
Slough SL3 6P1
United Kingdom

P. S. Hafskjold
Ing. F. Selmer AS
Post Office Box 256
Oslo, Norway

John D. Holst
Elkem-Spigerverk
Post Office Box 4224
Oslo 4, Norway

M. D. Haxwell
Sir Robert McAlpine & Sons, Ltd.
40 Bernard Street
London WC1
United Kingdom

KV. Swaminathan
Principal Scientist, Cement
Research Institute of India
M-10 South Extension II
Ring Road
New Delhi 49, India

K. H. Brittain
Chief Technical Consultant-Blue
Circle Group
Cement Marketing Company Ltd.
Portland House, Stag Place
London SW1, United Kingdom

Hans Richard Hansen
DET NORSKE VERITAS
Division of Marine Technology
P.O. Box 6060
Etterstadi, Oslo 6, Norway

Mr. Knut Hove
DET NORSKE VERITAS
Division of Marine Technology
P.O. Box 6060
Etterstadi, Oslo 6, Norway

S. B. Stubbs
Taylor, Woodrow Construction Ltd
345 Ruislip Road
Southall
Middlesex, England

Pierre Launay
Europe-Etudes
66 Route de la Reine
92 Boulogne-Bellancourt

Dr. Munther Haddadin
Royal Scientific Society
Amman, Jordan

<p>Civil Engineering Laboratory LONG-TERM DEEP-OCEAN TEST OF CONCRETE SPHERICAL STRUCTURES. Part I. Fabrication, Emplacement, and Initial Inspections, by Harvey H. Haynes TR-805 43 p. illus March 1974 Unclassified</p> <p>1. Submerged concrete structures 2. Seawater permeability of concrete 1. DOT 3.1610</p> <p>This report summarizes the fabrication, emplacement and inspections during the first 1.2 years of submergence of eighteen 66-inch-OD concrete spheres. The spheres are located 4 miles south of Santa Cruz Island, California, in depths of water from 1,840 to 5,075 feet. The purpose of the test is to collect data on time-dependent failure, permeability and durability of concrete pressure-resistant structures. Findings from the inspections showed that two spheres located at the depths of 3,725 and 4,330 feet had imploded and that the quantity of seawater which permeated through the concrete for phenolic-coated spheres was about 0.8 cu ft and for uncoated spheres it was about 1.6 cu ft. This test program is planned to continue through 1981 (total of 10 years).</p>	<p>Civil Engineering Laboratory LONG-TERM DEEP-OCEAN TEST OF CONCRETE SPHERICAL STRUCTURES. Part I. Fabrication, Emplacement, and Initial Inspections, by Harvey H. Haynes TR-805 43 p. illus March 1974 Unclassified</p> <p>1. Submerged concrete structures 2. Seawater permeability of concrete 1. DOT 3.1610</p> <p>This report summarizes the fabrication, emplacement and inspections during the first 1.2 years of submergence of eighteen 66-inch-OD concrete spheres. The spheres are located 4 miles south of Santa Cruz Island, California, in depths of water from 1,840 to 5,075 feet. The purpose of the test is to collect data on time-dependent failure, permeability and durability of concrete pressure-resistant structures. Findings from the inspections showed that two spheres located at the depths of 3,725 and 4,330 feet had imploded and that the quantity of seawater which permeated through the concrete for phenolic-coated spheres was about 0.8 cu ft and for uncoated spheres it was about 1.6 cu ft. This test program is planned to continue through 1981 (total of 10 years).</p>
<p>Civil Engineering Laboratory LONG-TERM DEEP-OCEAN TEST OF CONCRETE SPHERICAL STRUCTURES. Part I. Fabrication, Emplacement, and Initial Inspections, by Harvey H. Haynes TR-805 43 p. illus March 1974 Unclassified</p> <p>1. Submerged concrete structures 2. Seawater permeability of concrete 1. DOT 3.1610</p> <p>This report summarizes the fabrication, emplacement and inspections during the first 1.2 years of submergence of eighteen 66-inch-OD concrete spheres. The spheres are located 4 miles south of Santa Cruz Island, California, in depths of water from 1,840 to 5,075 feet. The purpose of the test is to collect data on time-dependent failure, permeability and durability of concrete pressure-resistant structures. Findings from the inspections showed that two spheres located at the depths of 3,725 and 4,330 feet had imploded and that the quantity of seawater which permeated through the concrete for phenolic-coated spheres was about 0.8 cu ft and for uncoated spheres it was about 1.6 cu ft. This test program is planned to continue through 1981 (total of 10 years).</p>	<p>Civil Engineering Laboratory LONG-TERM DEEP-OCEAN TEST OF CONCRETE SPHERICAL STRUCTURES. Part I. Fabrication, Emplacement, and Initial Inspections, by Harvey H. Haynes TR-805 43 p. illus March 1974 Unclassified</p> <p>1. Submerged concrete structures 2. Seawater permeability of concrete 1. DOT 3.1610</p> <p>This report summarizes the fabrication, emplacement and inspections during the first 1.2 years of submergence of eighteen 66-inch-OD concrete spheres. The spheres are located 4 miles south of Santa Cruz Island, California, in depths of water from 1,840 to 5,075 feet. The purpose of the test is to collect data on time-dependent failure, permeability and durability of concrete pressure-resistant structures. Findings from the inspections showed that two spheres located at the depths of 3,725 and 4,330 feet had imploded and that the quantity of seawater which permeated through the concrete for phenolic-coated spheres was about 0.8 cu ft and for uncoated spheres it was about 1.6 cu ft. This test program is planned to continue through 1981 (total of 10 years).</p>

<p>Civil Engineering Laboratory LONG-TERM DEEP-OCEAN TEST OF CONCRETE SPHERICAL STRUCTURES, Part I. Fabrication, Emplacement, and Initial Inspections, by Harvey H. Haynes TR-805 43 p. illus March 1974 Unclassified</p> <p>1. Submerged concrete structures 2. Seawater permeability of concrete I. DOT 3.1610</p> <p>This report summarizes the fabrication, emplacement and inspections during the first 1.2 years of submergence of eighteen 66-inch-OD concrete spheres. The spheres are located 4 miles south of Santa Cruz Island, California, in depths of water from 1,840 to 5,075 feet. The purpose of the test is to collect data on time-dependent failure, permeability and durability of concrete pressure-resistant structures. Findings from the inspections showed that two spheres located at the depths of 3,725 and 4,330 feet had imploded and that the quantity of seawater which permeated through the concrete for phenolic-coated spheres was about 0.8 cu ft and for uncoated spheres it was about 1.6 cu ft. This test program is planned to continue through 1981 (total of 10 years).</p>	<p>Civil Engineering Laboratory LONG-TERM DEEP-OCEAN TEST OF CONCRETE SPHERICAL STRUCTURES, Part I. Fabrication, Emplacement, and Initial Inspections, by Harvey H. Haynes TR-805 43 p. illus March 1974 Unclassified</p> <p>1. Submerged concrete structures 2. Seawater permeability of concrete I. DOT 3.1610</p> <p>This report summarizes the fabrication, emplacement and inspections during the first 1.2 years of submergence of eighteen 66-inch-OD concrete spheres. The spheres are located 4 miles south of Santa Cruz Island, California, in depths of water from 1,840 to 5,075 feet. The purpose of the test is to collect data on time-dependent failure, permeability and durability of concrete pressure-resistant structures. Findings from the inspections showed that two spheres located at the depths of 3,725 and 4,330 feet had imploded and that the quantity of seawater which permeated through the concrete for phenolic-coated spheres was about 0.8 cu ft and for uncoated spheres it was about 1.6 cu ft. This test program is planned to continue through 1981 (total of 10 years).</p>
<p>Civil Engineering Laboratory LONG-TERM DEEP-OCEAN TEST OF CONCRETE SPHERICAL STRUCTURES, Part I. Fabrication, Emplacement, and Initial Inspections, by Harvey H. Haynes TR-805 43 p. illus March 1974 Unclassified</p> <p>1. Submerged concrete structures 2. Seawater permeability of concrete I. DOT 3.1610</p> <p>This report summarizes the fabrication, emplacement and inspections during the first 1.2 years of submergence of eighteen 66-inch-OD concrete spheres. The spheres are located 4 miles south of Santa Cruz Island, California, in depths of water from 1,840 to 5,075 feet. The purpose of the test is to collect data on time-dependent failure, permeability and durability of concrete pressure-resistant structures. Findings from the inspections showed that two spheres located at the depths of 3,725 and 4,330 feet had imploded and that the quantity of seawater which permeated through the concrete for phenolic-coated spheres was about 0.8 cu ft and for uncoated spheres it was about 1.6 cu ft. This test program is planned to continue through 1981 (total of 10 years).</p>	<p>Civil Engineering Laboratory LONG-TERM DEEP-OCEAN TEST OF CONCRETE SPHERICAL STRUCTURES, Part I. Fabrication, Emplacement, and Initial Inspections, by Harvey H. Haynes TR-805 43 p. illus March 1974 Unclassified</p> <p>1. Submerged concrete structures 2. Seawater permeability of concrete I. DOT 3.1610</p> <p>This report summarizes the fabrication, emplacement and inspections during the first 1.2 years of submergence of eighteen 66-inch-OD concrete spheres. The spheres are located 4 miles south of Santa Cruz Island, California, in depths of water from 1,840 to 5,075 feet. The purpose of the test is to collect data on time-dependent failure, permeability and durability of concrete pressure-resistant structures. Findings from the inspections showed that two spheres located at the depths of 3,725 and 4,330 feet had imploded and that the quantity of seawater which permeated through the concrete for phenolic-coated spheres was about 0.8 cu ft and for uncoated spheres it was about 1.6 cu ft. This test program is planned to continue through 1981 (total of 10 years).</p>