Plan of

Director's Bungalow
and its Cost

1867

Presented by Mr. W. E. Hooper.

Oh Meng's Estimate for the Building of the proposed dwelling for the Superintendent of the U. S. Society's Garden

220	Saros beams for joists	22 feet long 6 inch square	\$200.00
8	Lampun	28 feet long 8 by 9 inch square	56.00
12	"	22 " "	60.00
16	"	26 " 7 " "	48.00
36	"	22 " 6 " "	90.00
452	Flooring planks	9 inch broad 1 1/4 inch thick	112.00
3000	Lathing	" " " 3/4 " "	210.00
220	Saraya Roofing timbers	16 feet by 3 1/2 inch square	50.00
750	Tiling Rafter	16 " 1 1/4 thick	52.00
100	Buntang joists for ceiling		2.00
	Planks for 34 doors	\$25 - 8000 Roofing tiles	200.00
3000	Square Tiles	\$90 - 50 Cozans tiles \$100 - 6000 tiles \$140 -	230.00
	Angus screw nails bolts & works		20.00
	Nails with bolts for cupols		10.00
	Granite stones for setting pillars on		16.00
	Granite Slabs for steps		150.00
	Scaffolding \$60 - Cart hire \$100 -		45.00
	Planks for 34 doors		20.00
	Whitewashing and painting		25.00
	Labour		10.00

是此屋料

If the flooring joists and the principal cupols
are of Lampun's wood instead of Saros the cost
will be \$180 more

Singapore, 10th June 1880

Foundation Pillars, Walls, Roof, etc.

Strong 50 Ceiling

29

8137/3

3134/3

From Whom

Place

Date

Director Linn

Former Papers.

MINUTES.

Final Paper.

Plan, not carried out
Estimate

No Minutes should be written on this page. A separate half-sheet
to be used if required.